



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
CORPS OF ENGINEERS, OMAHA DISTRICT
HELENA REGULATORY OFFICE
10 WEST 15TH STREET, SUITE 2200
HELENA, MONTANA 59626

November 7, 2017

Regulatory Branch
Montana State Program
Corps No. **NWO-2016-00179-MTH**

Subject: Wade Crittenden - Culvert Replacement - Stickney Creek (Lewis and Clark County)

Deanna Lane
Montana Recreational Properties, Inc.
PO Box 69
Deer Lodge, Montana 59722

Dear Ms. Lane:

We are responding to your request for Nationwide Permit (NWP) verification for the above-mentioned project. The project is located at Latitude 47.09194°, Longitude -111.90311°, on Stickney Creek, within Section 6, Township 15 N, Range 2 W, Lewis and Clark County, Montana.

Specifically, you requested authorization for the following work in waters of the U.S.:

Work Item	Description
a.	Two (2) existing 24-inch culverts will be replaced with two (2) 60-inch by 10-foot long culverts. Approximately 18 cubic yards of 6-12-inch riprap will be used on either side of the culverts.

Based on the information you provided, the proposed activity, [permanently or temporarily] affecting approximately 10 linear feet of Stickney Creek, is authorized by NWP 14, found in the January 6, 2017, Federal Register (82 FR 1860), Reissuance of Nationwide Permits. Enclosed is a fact sheet that fully describes this NWP and lists the General and Regional Conditions that must be adhered to for this authorization to remain valid. Please note that deviations from the original plans and specifications of your project could require additional authorization from this office.

You are responsible for ensuring that all work is performed in accordance with the terms and conditions of the NWP. If a contractor or other authorized representative will be conducting work on your behalf it is strongly recommended that they be provided a copy of this letter and the enclosed conditions. Failure to comply with the General and Regional Conditions of this NWP, may result in the suspension or revocation of your authorization and may be subject to appropriate enforcement action.

The Montana Department of Environmental Quality has provided the enclosed CWA Section 401 water quality certification for this NWP which includes General Conditions, all of which must be complied with for that certification to remain valid. This does not eliminate the need to obtain other permits that may be required by that agency.

COMPLIANCE CERTIFICATION

Corps File Number: NWO-2016-00179-MTH
Permit Type: NWP 14
Name of Permittee: Deanna Lane
County: Lewis and Clark County, Montana
Date of Issuance: November 7, 2017
Corps Project Manager: Timothy McNew

Upon completion of the activity authorized by this permit and any mitigation required by the permit, sign this certification and return it to the following address:

US Army Corps of Engineers
Omaha District
Helena Regulatory Office
10 West 15 Street, Suite 2200
Helena, Montana 59626

Please note that your permitted activity is subject to a compliance inspection by a U.S. Army Corps of Engineers representative. If you fail to comply with the conditions of this permit, you are subject to permit suspension, modification, or revocation.

I hereby certify that the work authorized by the above referenced permit has been completed in accordance with the terms and conditions of the said permit, and required mitigation was completed in accordance with the permit conditions.

Signature of Permittee



March 6, 2017

Robert Cole
Corps of Engineers, Helena Regulatory Office
10 West 15th Street, Suite 2200
Helena, Montana 59626

Re: Montana Department of Environmental Quality 401 Water Quality Certification (COE-2015-0017 RIN 0710-AA73-2017 Nationwide Permit Reissuance-Federal Register Vol. 82 No. 4)

Dear Mr. Cole:

The attachment to this letter (Parts A-E) constitutes the Montana Department of Environmental Quality's position on the subject Nationwide Permits. It should not result in an undue burden to either of our agencies, while still providing adequate water quality protection. Also, please find enclosed the Montana Department of Environmental Quality's December 5, 2000, guidelines for materials for stream bank stabilization as referenced in the attached certification.

We look forward to continuing the close cooperation and coordination between our two agencies. Please do not hesitate to contact myself (444-0240 JKenning@mt.gov) or Jason Garber (444-2734 JGarber2@mt.gov) if you have any questions.

Sincerely,

A handwritten signature in black ink, appearing to read "Jon Kenning", is written over the typed name.

Jon Kenning-Chief
Water Protection Bureau

Cc: Tony Ott-EPA w/ Attachments

E. General Conditions for Nationwide Permits

The following general conditions apply to all certified Nationwide Permits as provided in A and B above.

- 1) This certification does not authorize the placement or construction of septic/leach systems or other sewage treatment facilities in wetlands.
- 2) This certification does not authorize construction of dams, except for aquatic restoration projects and temporary dams associated with construction activity.
- 3) This certification requires that materials used in stream bank or shore stabilization projects adhere to the Montana Department of Environmental Quality's December 5, 2000 guidelines for materials for stream bank stabilization. Tires may not be used to stabilize any banks in state waters.
- 4) This certification requires that all equipment be inspected for oil, gas, diesel, anti-freeze, hydraulic fluid and other petroleum leaks. Equipment cannot continue operating in or near the water if a leak is discovered. All such leaks will be properly repaired prior to equipment being allowed on the project site. Leaks that occur after the equipment is moved to the project site will be fixed that same day or the next day or be removed from the project area. If equipment is to be operated in or near water, a spill containment kit shall be available at the project site and DEQ shall be notified of spills.
- 5) This certification requires that all permittees shall, to the maximum extent practicable, incorporate and construct design features that eliminate bridge deck run-off containing sediment, salt, or other pollutants from discharging directly into state water. To the extent practicable, bridge deck run-off, should be directed to a detention basin of unspecified size prior to continuing into state waters.
- 6) This certification requires that riprap projects, to the extent practicable, avoid the use of geotextile fabric as riprap bedding material. To the extent practicable, riprap voids shall incorporate approximately 30-50% fines/soil and dormant plant material and/or root-stock.

F. Reopener Clause

DEQ reserves the right to add or alter terms and conditions as appropriate to carry out its responsibilities with respect to water quality throughout the five year Nationwide Permit Cycle.

COMPLIANCE CERTIFICATION

Project: (Please attach copy of the completed "Joint Application for Proposed Work in Montana's Streams, Wetlands, Floodplains, and Other Water Bodies.")

Upon completion of project activity, sign this certificate and return it to the following address:

Montana Department of Environmental Quality
Permitting & Compliance Division/Water Protection Bureau
Box 200901
Helena, MT 59620-0901

Please answer the following questions:

1. What is the source of the concrete rubble?
2. What is the type of concrete rubble (curb/gutter, foundation, etc.)?
3. What was the cost of the rubble?
(The recipient of the rubble cannot be compensated for accepting the rubble without a landfill license.)

I hereby certify that the project work performed is in compliance with all applicable permits and in compliance with the "Guidelines for Materials for Streambank Stabilization."

Signature of Project Owner	Date
----------------------------	------

I hereby certify that I provided the concrete rubble used in the project and that I did not compensate the owner for accepting the rubble.

Signature of Concrete Rubble Provider	Date
---------------------------------------	------

Nationwide Permit 14

Linear Transportation Projects

Activities required for crossings of waters of the United States associated with the construction, expansion, modification, or improvement of linear transportation projects (e.g., roads, highways, railways, trails, airport runways, and taxiways) in waters of the United States. For linear transportation projects in non-tidal waters, the discharge cannot cause the loss of greater than 1/2-acre of waters of the United States. For linear transportation projects in tidal waters, the discharge cannot cause the loss of greater than 1/3-acre of waters of the United States.

Any stream channel modification, including bank stabilization, is limited to the minimum necessary to construct or protect the linear transportation project; such modifications must be in the immediate vicinity of the project.

This NWP also authorizes temporary structures, fills, and work, including the use of temporary mats, necessary to construct the linear transportation project. Appropriate measures must be taken to maintain normal downstream flows and minimize flooding to the maximum extent practicable, when temporary structures, work, and discharges, including cofferdams, are necessary for construction activities, access fills, or dewatering of construction sites. Temporary fills must consist of materials, and be placed in a manner, that will not be eroded by expected high flows. Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The areas affected by temporary fills must be revegetated, as appropriate.

This NWP cannot be used to authorize non-linear features commonly associated with transportation projects, such as vehicle maintenance or storage buildings, parking lots, train stations, or aircraft hangars.

Notification: The permittee must submit a pre-construction notification to the district engineer prior to commencing the activity if: (1) The loss of waters of the United States exceeds 1/10-acre; or (2) there is a discharge in a special aquatic site, including wetlands. (See general condition 32.)

(Authorities: Sections 10 and 404)

Note 1: For linear transportation projects crossing a single waterbody more than one time at separate and distant locations, or multiple waterbodies at separate and distant locations, each crossing is considered a single and complete project for purposes of NWP authorization. Linear transportation projects must comply with 33 CFR 330.6(d).

Note 2: Some discharges for the construction of farm roads or forest roads, or temporary roads for moving mining equipment, may qualify for an exemption under section 404(f) of the Clean Water Act (see 33 CFR 323.4).

Note 3: For NWP 14 activities that require pre-construction notification, the PCN must include any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings that require Department of the Army authorization but do not require pre-construction notification (see paragraph (b) of general condition 32). The district engineer will evaluate the PCN in accordance with Section D, "District Engineer's Decision." The district engineer may require mitigation to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see general condition 23).

Nationwide Permit General Conditions

Note: To qualify for NWP authorization, the prospective permittee must comply with the following general conditions, as applicable, in addition to any regional or case-specific conditions imposed by the division

engineer or district engineer. Prospective permittees should contact the appropriate Corps district office to determine if regional conditions have been imposed on an NWP. Prospective permittees should also contact the appropriate Corps district office to determine the status of Clean Water Act Section 401 water quality certification and/ or Coastal Zone Management Act consistency for an NWP. Every person who may wish to obtain permit authorization under one or more NWPs, or who is currently relying on an existing or prior permit authorization under one or more NWPs, has been and is on notice that all of the provisions of 33 CFR 330.1 through 330.6 apply to every NWP authorization. Note especially 33 CFR 330.5 relating to the modification, suspension, or revocation of any NWP authorization.

1. Navigation.

- (a) No activity may cause more than a minimal adverse effect on navigation.
- (b) Any safety lights and signals prescribed by the U.S. Coast Guard, through regulations or otherwise, must be installed and maintained at the permittee's expense on authorized facilities in navigable waters of the United States.
- (c) The permittee understands and agrees that, if future operations by the United States require the removal, relocation, or other alteration, of the structure or work herein authorized, or if, in the opinion of the Secretary of the Army or his authorized representative, said structure or work shall cause unreasonable obstruction to the free navigation of the navigable waters, the permittee will be required, upon due notice from the Corps of Engineers, to remove, relocate, or alter the structural work or obstructions caused thereby, without expense to the United States. No claim shall be made against the United States on account of any such removal or alteration.

2. Aquatic Life Movements.

No activity may substantially disrupt the necessary life cycle movements of those species of aquatic life indigenous to the waterbody, including those species that normally migrate through the area, unless the activity's primary purpose is to impound water. All permanent and temporary crossings of waterbodies shall be suitably culverted, bridged, or otherwise designed and constructed to maintain low flows to sustain the movement of those aquatic species. If a bottomless culvert cannot be used, then the crossing should be designed and constructed to minimize adverse effects to aquatic life movements.

3. Spawning Areas.

Activities in spawning areas during spawning seasons must be avoided to the maximum extent practicable. Activities that result in the physical destruction (e.g., through excavation, fill, or downstream smothering by substantial turbidity) of an important spawning area are not authorized.

4. Migratory Bird Breeding Areas.

Activities in waters of the United States that serve as breeding areas for migratory birds must be avoided to the maximum extent practicable.

5. Shellfish Beds.

No activity may occur in areas of concentrated shellfish populations, unless the activity is directly related to a shellfish harvesting activity authorized by NWPs 4 and 48, or is a shellfish seeding or habitat restoration activity authorized by NWP 27.

6. Suitable Material.

No activity may use unsuitable material (e.g., trash, debris, car bodies, asphalt, etc.). Material used for construction or discharged must be free from toxic pollutants in toxic amounts (see section 307 of the Clean Water Act).

7. Water Supply Intakes.

No activity may occur in the proximity of a public water supply intake, except where the activity is for the repair or improvement of public water supply intake structures or adjacent bank stabilization.

8. Adverse Effects from Impoundments.

If the activity creates an impoundment of water, adverse effects to the aquatic system due to accelerating the passage of water, and/or restricting its flow must be minimized to the maximum extent practicable.

9. Management of Water Flows.

To the maximum extent practicable, the pre-construction course, condition, capacity, and location of open waters must be maintained for each activity, including stream channelization, storm water management activities, and temporary and permanent road crossings, except as provided below. The activity must be constructed to withstand expected high flows. The activity must not restrict or impede the passage of normal or high flows, unless the primary purpose of the activity is to impound water or manage high flows. The activity may alter the pre-construction course, condition, capacity, and location of open waters if it benefits the aquatic environment (e.g., stream restoration or relocation activities).

10. Fills Within 100-Year Floodplains.

The activity must comply with applicable FEMA-approved state or local floodplain management requirements.

11. Equipment.

Heavy equipment working in wetlands or mudflats must be placed on mats, or other measures must be taken to minimize soil disturbance.

12. Soil Erosion and Sediment Controls.

Appropriate soil erosion and sediment controls must be used and maintained in effective operating condition during construction, and all exposed soil and other fills, as well as any work below the ordinary high water mark or high tide line, must be permanently stabilized at the earliest practicable date. Permittees are encouraged to perform work within waters of the United States during periods of low-flow or no-flow, or during low tides.

13. Removal of Temporary Fills.

Temporary fills must be removed in their entirety and the affected areas returned to pre-construction elevations. The affected areas must be revegetated, as appropriate.

14. Proper Maintenance.

Any authorized structure or fill shall be properly maintained, including maintenance to ensure public safety and compliance with applicable NWP general conditions, as well as any activity-specific conditions added by the district engineer to an NWP authorization.

15. Single and Complete Project.

The activity must be a single and complete project. The same NWP cannot be used more than once for the same single and complete project.

16. Wild and Scenic Rivers.

(a) No NWP activity may occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, unless the appropriate Federal agency with direct management responsibility for such river, has determined in writing that the proposed activity will not adversely affect the Wild and Scenic River designation or study status.

(b) If a proposed NWP activity will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, the permittee must submit a pre-construction notification (see general condition 32). The district engineer will coordinate the PCN with the Federal agency with direct management responsibility for that river. The permittee shall not begin the NWP activity until notified by the district engineer that the Federal agency with direct management responsibility for that river has determined in writing that the proposed NWP activity will not adversely affect the Wild and Scenic River designation or study status.

(c) Information on Wild and Scenic Rivers may be obtained from the appropriate Federal land management agency responsible for the designated Wild and Scenic River or study river (e.g., National Park Service, U.S. Forest Service, Bureau of Land Management, U.S. Fish and Wildlife Service). Information on these rivers is also available at: <http://www.rivers.gov/>.

17. Tribal Rights.

No NWP activity may cause more than minimal adverse effects on tribal rights (including treaty rights), protected tribal resources, or tribal lands.

18. Endangered Species.

(a) No activity is authorized under any NWP which is likely to directly or indirectly jeopardize the continued existence of a threatened or endangered species or a species proposed for such designation, as identified under the Federal Endangered Species Act (ESA), or which will directly or indirectly destroy or adversely modify the critical habitat of such species. No activity is authorized under any NWP which "may affect" a listed species or critical habitat, unless ESA section 7 consultation addressing the effects of the proposed activity has been completed. Direct effects are the immediate effects on listed species and critical habitat caused by the NWP activity. Indirect effects are those effects on listed species and critical habitat that are caused by the NWP activity and are later in time, but still are reasonably certain to occur.

(b) Federal agencies should follow their own procedures for complying with the requirements of the ESA. If pre-construction notification is required for the proposed activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation has not been submitted, additional ESA section 7 consultation may be necessary for the activity and the respective federal agency would be responsible for fulfilling its obligation under section 7 of the ESA.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if any listed species or designated critical habitat might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat, and shall not begin work on the activity until notified by the district engineer that the requirements of the ESA have been satisfied and that the activity is authorized. For activities that might affect Federally-listed endangered or threatened species or designated critical habitat, the pre-construction notification must include the name(s) of the endangered or threatened species that might be affected by the proposed activity or that utilize the designated critical habitat that might be affected by the proposed activity. The district engineer will determine whether the proposed activity "may affect" or will have "no effect" to listed species and designated critical habitat and will notify the non-Federal applicant of the Corps' determination within 45 days of receipt of a complete pre-construction notification. In cases where the non-Federal applicant has identified listed species or critical habitat that might be affected or is in the vicinity of the activity, and has so notified the Corps, the applicant shall not begin work until the Corps has provided notification that the proposed activity will have

"no effect" on listed species or critical habitat, or until ESA section 7 consultation has been completed. If the non-Federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(d) As a result of formal or informal consultation with the FWS or NMFS the district engineer may add species- specific permit conditions to the NWP.

(e) Authorization of an activity by an NWP does not authorize the "take" of a threatened or endangered species as defined under the ESA. In the absence of separate authorization (e.g., an ESA Section 10 Permit, a Biological Opinion with "incidental take" provisions, etc.) from the FWS or the NMFS, the Endangered Species Act prohibits any person subject to the jurisdiction of the United States to take a listed species, where "take" means to harass, harm, pursue, hunt, shoot, wound, kill, trap, capture, or collect, or to attempt to engage in any such conduct. The word "harm" in the definition of "take" means an act which actually kills or injures wildlife. Such an act may include significant habitat modification or degradation where it actually kills or injures wildlife by significantly impairing essential behavioral patterns, including breeding, feeding or sheltering.

(f) If the non-federal permittee has a valid ESA section 10(a)(1)(B) incidental take permit with an approved Habitat Conservation Plan for a project or a group of projects that includes the proposed NWP activity, the non-federal applicant should provide a copy of that ESA section 10(a)(1)(B) permit with the PCN required by paragraph (c) of this general condition. The district engineer will coordinate with the agency that issued the ESA section 10(a)(1)(B) permit to determine whether the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation conducted for the ESA section 10(a)(1)(B) permit. If that coordination results in concurrence from the agency that the proposed NWP activity and the associated incidental take were considered in the internal ESA section 7 consultation for the ESA section 10(a)(1)(B) permit, the district engineer does not need to conduct a separate ESA section 7 consultation for the proposed NWP activity. The district engineer will notify the non-federal applicant within 45 days of receipt of a complete pre-construction notification whether the ESA section 10(a)(1)(B) permit covers the proposed NWP activity or whether additional ESA section 7 consultation is required.

(g) Information on the location of threatened and endangered species and their critical habitat can be obtained directly from the offices of the FWS and NMFS or their world wide Web pages at <http://www.fws.gov/> or <http://www.fws.gov/ipac> and <http://www.nmfs.noaa.gov/pr/species/esa/> respectively.

19. Migratory Birds and Bald and Golden Eagles.

The permittee is responsible for ensuring their action complies with the Migratory Bird Treaty Act and the Bald and Golden Eagle Protection Act. The permittee is responsible for contacting appropriate local office of the U.S. Fish and Wildlife Service to determine applicable measures to reduce impacts to migratory birds or eagles, including whether "incidental take" permits are necessary and available under the Migratory Bird Treaty Act or Bald and Golden Eagle Protection Act for a particular activity.

20. Historic Properties.

(a) In cases where the district engineer determines that the activity may have the potential to cause effects to properties listed, or eligible for listing, in the National Register of Historic Places, the activity is not authorized, until the requirements of Section 106 of the National Historic Preservation Act (NHPA) have been satisfied.

(b) Federal permittees should follow their own procedures for complying with the requirements of section 106 of the National Historic Preservation Act. If pre-construction notification is required for the proposed NWP activity, the Federal permittee must provide the district engineer with the appropriate documentation to demonstrate compliance with those requirements. The district engineer will verify that the appropriate documentation has been submitted. If the appropriate documentation is not submitted, then additional consultation under section 106 may be necessary. The respective federal agency is responsible for fulfilling its obligation to comply with section 106.

(c) Non-federal permittees must submit a pre-construction notification to the district engineer if the NWP activity might have the potential to cause effects to any historic properties listed on, determined to be eligible for listing on, or potentially eligible for listing on the National Register of Historic Places, including

previously unidentified properties. For such activities, the pre-construction notification must state which historic properties might have the potential to be affected by the proposed NWP activity or include a vicinity map indicating the location of the historic properties or the potential for the presence of historic properties. Assistance regarding information on the location of, or potential for, the presence of historic properties can be sought from the State Historic Preservation Officer, Tribal Historic Preservation Officer, or designated tribal representative, as appropriate, and the National Register of Historic Places (see 33 CFR 330.4(g)). When reviewing pre-construction notifications, district engineers will comply with the current procedures for addressing the requirements of section 106 of the National Historic Preservation Act. The district engineer shall make a reasonable and good faith effort to carry out appropriate identification efforts, which may include background research, consultation, oral history interviews, sample field investigation, and field survey. Based on the information submitted in the PCN and these identification efforts, the district engineer shall determine whether the proposed NWP activity has the potential to cause effects on the historic properties. Section 106 consultation is not required when the district engineer determines that the activity does not have the potential to cause effects on historic properties (see 36 CFR 800.3(a)). Section 106 consultation is required when the district engineer determines that the activity has the potential to cause effects on historic properties. The district engineer will conduct consultation with consulting parties identified under 36 CFR 800.2(c) when he or she makes any of the following effect determinations for the purposes of section 106 of the NHPA: no historic properties affected, no adverse effect, or adverse effect. Where the non-Federal applicant has identified historic properties on which the activity might have the potential to cause effects and so notified the Corps, the non-Federal applicant shall not begin the activity until notified by the district engineer either that the activity has no potential to cause effects to historic properties or that NHPA section 106 consultation has been completed.

(d) For non-federal permittees, the district engineer will notify the prospective permittee within 45 days of receipt of a complete pre-construction notification whether NHPA section 106 consultation is required. If NHPA section 106 consultation is required, the district engineer will notify the non-Federal applicant that he or she cannot begin the activity until section 106 consultation is completed. If the non-Federal applicant has not heard back from the Corps within 45 days, the applicant must still wait for notification from the Corps.

(e) Prospective permittees should be aware that section 110k of the NHPA (54 U.S.C. 306113) prevents the Corps from granting a permit or other assistance to an applicant who, with intent to avoid the requirements of section 106 of the NHPA, has intentionally significantly adversely affected a historic property to which the permit would relate, or having legal power to prevent it, allowed such significant adverse effect to occur, unless the Corps, after consultation with the Advisory Council on Historic Preservation (ACHP), determines that circumstances justify granting such assistance despite the adverse effect created or permitted by the applicant. If circumstances justify granting the assistance, the Corps is required to notify the ACHP and provide documentation specifying the circumstances, the degree of damage to the integrity of any historic properties affected, and proposed mitigation. This documentation must include any views obtained from the applicant, SHPO/ THPO, appropriate Indian tribes if the undertaking occurs on or affects historic properties on tribal lands or affects properties of interest to those tribes, and other parties known to have a legitimate interest in the impacts to the permitted activity on historic properties.

21. Discovery of Previously Unknown Remains and Artifacts.

If you discover any previously unknown historic, cultural or archeological remains and artifacts while accomplishing the activity authorized by this permit, you must immediately notify the district engineer of what you have found, and to the maximum extent practicable, avoid construction activities that may affect the remains and artifacts until the required coordination has been completed. The district engineer will initiate the Federal, Tribal, and state coordination required to determine if the items or remains warrant a recovery effort or if the site is eligible for listing in the National Register of Historic Places.

22. Designated Critical Resource Waters.

Critical resource waters include, NOAA-managed marine sanctuaries and marine monuments, and National Estuarine Research Reserves. The district engineer may designate, after notice and opportunity

for public comment, additional waters officially designated by a state as having particular environmental or ecological significance, such as outstanding national resource waters or state natural heritage sites. The district engineer may also designate additional critical resource waters after notice and opportunity for public comment.

(a) Discharges of dredged or fill material into waters of the United States are not authorized by NWPs 7, 12, 14, 16, 17, 21, 29, 31, 35, 39, 40, 42, 43, 44, 49, 50, 51, and 52 for any activity within, or directly affecting, critical resource waters, including wetlands adjacent to such waters.

(b) For NWPs 3, 8, 10, 13, 15, 18, 19, 22, 23, 25, 27, 28, 30, 33, 34, 36, 37, 38, and 54, notification is required in accordance with general condition 32, for any activity proposed in the designated critical resource waters including wetlands adjacent to those waters. The district engineer may authorize activities under these NWPs only after it is determined that the impacts to the critical resource waters will be no more than minimal.

23. Mitigation.

The district engineer will consider the following factors when determining appropriate and practicable mitigation necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal:

(a) The activity must be designed and constructed to avoid and minimize adverse effects, both temporary and permanent, to waters of the United States to the maximum extent practicable at the project site (i.e., on site).

(b) Mitigation in all its forms (avoiding, minimizing, rectifying, reducing, or compensating for resource losses) will be required to the extent necessary to ensure that the individual and cumulative adverse environmental effects are no more than minimal.

(c) Compensatory mitigation at a minimum one-for-one ratio will be required for all wetland losses that exceed 1/10-acre and require pre-construction notification, unless the district engineer determines in writing that either some other form of mitigation would be more environmentally appropriate or the adverse environmental effects of the proposed activity are no more than minimal, and provides an activity-specific waiver of this requirement. For wetland losses of 1/10-acre or less that require pre-construction notification, the district engineer may determine on a case-by-case basis that compensatory mitigation is required to ensure that the activity results in only minimal adverse environmental effects.

(d) For losses of streams or other open waters that require pre-construction notification, the district engineer may require compensatory mitigation to ensure that the activity results in no more than minimal adverse environmental effects. Compensatory mitigation for losses of streams should be provided, if practicable, through stream rehabilitation, enhancement, or preservation, since streams are difficult-to-replace resources (see 33 CFR 332.3(e)(3)).

(e) Compensatory mitigation plans for NWP activities in or near streams or other open waters will normally include a requirement for the restoration or enhancement, maintenance, and legal protection (e.g., conservation easements) of riparian areas next to open waters. In some cases, the restoration or maintenance/protection of riparian areas may be the only compensatory mitigation required. Restored riparian areas should consist of native species. The width of the required riparian area will address documented water quality or aquatic habitat loss concerns.

Normally, the riparian area will be 25 to 50 feet wide on each side of the stream, but the district engineer may require slightly wider riparian areas to address documented water quality or habitat loss concerns. If it is not possible to restore or maintain/protect a riparian area on both sides of a stream, or if the waterbody is a lake or coastal waters, then restoring or maintaining/protecting a riparian area along a single bank or shoreline may be sufficient. Where both wetlands and open waters exist on the project site, the district engineer will determine the appropriate compensatory mitigation (e.g., riparian areas and/or wetlands compensation) based on what is best for the aquatic environment on a watershed basis. In cases where riparian areas are determined to be the most appropriate form of minimization or compensatory mitigation, the district engineer may waive or reduce the requirement to provide wetland compensatory mitigation for wetland losses.

(f) Compensatory mitigation projects provided to offset losses of aquatic resources must comply with the applicable provisions of 33 CFR part 332.

(1) The prospective permittee is responsible for proposing an appropriate compensatory mitigation option if compensatory mitigation is necessary to ensure that the activity results in no more

than minimal adverse environmental effects. For the NWP, the preferred mechanism for providing compensatory mitigation is mitigation bank credits or in-lieu fee program credits (see 33 CFR 332.3(b)(2) and (3)). However, if an appropriate number and type of mitigation bank or in-lieu credits are not available at the time the PCN is submitted to the district engineer, the district engineer may approve the use of permittee-responsible mitigation.

(2) The amount of compensatory mitigation required by the district engineer must be sufficient to ensure that the authorized activity results in no more than minimal individual and cumulative adverse environmental effects (see 33 CFR 330.1(e)(3)). (See also 33 CFR 332.3(f)).

(3) Since the likelihood of success is greater and the impacts to potentially valuable uplands are reduced, aquatic resource restoration should be the first compensatory mitigation option considered for permittee-responsible mitigation.

(4) If permittee-responsible mitigation is the proposed option, the prospective permittee is responsible for submitting a mitigation plan. A conceptual or detailed mitigation plan may be used by the district engineer to make the decision on the NWP verification request, but a final mitigation plan that addresses the applicable requirements of 33 CFR 332.4(c)(2) through (14) must be approved by the district engineer before the permittee begins work in waters of the United States, unless the district engineer determines that prior approval of the final mitigation plan is not practicable or not necessary to ensure timely completion of the required compensatory mitigation (see 33 CFR 332.3(k)(3)).

(5) If mitigation bank or in-lieu fee program credits are the proposed option, the mitigation plan only needs to address the baseline conditions at the impact site and the number of credits to be provided.

(6) Compensatory mitigation requirements (e.g., resource type and amount to be provided as compensatory mitigation, site protection, ecological performance standards, monitoring requirements) may be addressed through conditions added to the NWP authorization, instead of components of a compensatory mitigation plan (see 33 CFR 332.4(c)(1)(ii)).

(g) Compensatory mitigation will not be used to increase the acreage losses allowed by the acreage limits of the NWPs. For example, if an NWP has an acreage limit of 1/2-acre, it cannot be used to authorize any NWP activity resulting in the loss of greater than 1/2-acre of waters of the United States, even if compensatory mitigation is provided that replaces or restores some of the lost waters. However, compensatory mitigation can and should be used, as necessary, to ensure that an NWP activity already meeting the established acreage limits also satisfies the no more than minimal impact requirement for the NWPs.

(h) Permittees may propose the use of mitigation banks, in-lieu fee programs, or permittee-responsible mitigation. When developing a compensatory mitigation proposal, the permittee must consider appropriate and practicable options consistent with the framework at 33 CFR 332.3(b). For activities resulting in the loss of marine or estuarine resources, permittee-responsible mitigation may be environmentally preferable if there are no mitigation banks or in-lieu fee programs in the area that have marine or estuarine credits available for sale or transfer to the permittee. For permittee-responsible mitigation, the special conditions of the NWP verification must clearly indicate the party or parties responsible for the implementation and performance of the compensatory mitigation project, and, if required, its long-term management.

(i) Where certain functions and services of waters of the United States are permanently adversely affected by a regulated activity, such as discharges of dredged or fill material into waters of the United States that will convert a forested or scrub-shrub wetland to a herbaceous wetland in a permanently maintained utility line right-of-way, mitigation may be required to reduce the adverse environmental effects of the activity to the no more than minimal level.

24. Safety of Impoundment Structures.

To ensure that all impoundment structures are safely designed, the district engineer may require non-Federal applicants to demonstrate that the structures comply with established state dam safety criteria or have been designed by qualified persons. The district engineer may also require documentation that the design has been independently reviewed by similarly qualified persons, and appropriate modifications made to ensure safety.

25. Water Quality.

Where States and authorized Tribes, or EPA where applicable, have not previously certified compliance of an NWP with CWA section 401, individual 401 Water Quality Certification must be obtained or waived (see 33 CFR 330.4(c)). The district engineer or State or Tribe may require additional water quality management measures to ensure that the authorized activity does not result in more than minimal degradation of water quality.

26. Coastal Zone Management.

In coastal states where an NWP has not previously received a state coastal zone management consistency concurrence, an individual state coastal zone management consistency concurrence must be obtained, or a presumption of concurrence must occur (see 33 CFR 330.4(d)). The district engineer or a State may require additional measures to ensure that the authorized activity is consistent with state coastal zone management requirements.

27. Regional and Case-By-Case Conditions.

The activity must comply with any regional conditions that may have been added by the Division Engineer (see 33 CFR 330.4(e)) and with any case specific conditions added by the Corps or by the state, Indian Tribe, or U.S. EPA in its section 401 Water Quality Certification, or by the state in its Coastal Zone Management Act consistency determination.

28. Use of Multiple Nationwide Permits.

The use of more than one NWP for a single and complete project is prohibited, except when the acreage loss of waters of the United States authorized by the NWPs does not exceed the acreage limit of the NWP with the highest specified acreage limit. For example, if a road crossing over tidal waters is constructed under NWP 14, with associated bank stabilization authorized by NWP 13, the maximum acreage loss of waters of the United States for the total project cannot exceed 1/3-acre.

29. Transfer of Nationwide Permit Verifications.

If the permittee sells the property associated with a nationwide permit verification, the permittee may transfer the nationwide permit verification to the new owner by submitting a letter to the appropriate Corps district office to validate the transfer. A copy of the nationwide permit verification must be attached to the letter, and the letter must contain the following statement and signature:

When the structures or work authorized by this nationwide permit are still in existence at the time the property is transferred, the terms and conditions of this nationwide permit, including any special conditions, will continue to be binding on the new owner(s) of the property. To validate the transfer of this nationwide permit and the associated liabilities associated with compliance with its terms and conditions, have the transferee sign and date below.

_____ (Transferee) _____ (Date)

30. Compliance Certification.

Each permittee who receives an NWP verification letter from the Corps must provide a signed certification documenting completion of the authorized activity and implementation of any required compensatory mitigation. The success of any required permittee-responsible mitigation, including the achievement of ecological performance standards, will be addressed separately by the district engineer. The Corps will provide the permittee the certification document with the NWP verification letter. The certification document will include:

(a) A statement that the authorized activity was done in accordance with the NWP authorization, including any general, regional, or activity-specific conditions;

(b) A statement that the implementation of any required compensatory mitigation was completed in accordance with the permit conditions. If credits from a mitigation bank or in-lieu fee program are used to satisfy the compensatory mitigation requirements, the certification must include the documentation required by 33 CFR 332.3(l)(3) to confirm that the permittee secured the appropriate number and resource type of credits; and

(c) The signature of the permittee certifying the completion of the activity and mitigation. The completed certification document must be submitted to the district engineer within 30 days of completion of the authorized activity or the implementation of any required compensatory mitigation, whichever occurs later.

31. Activities Affecting Structures or Works Built by the United States.

If an NWP activity also requires permission from the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers (USACE) federally authorized Civil Works project (a "USACE project"), the prospective permittee must submit a pre-construction notification. See paragraph (b)(10) of general condition 32. An activity that requires section 408 permission is not authorized by NWP until the appropriate Corps office issues the section 408 permission to alter, occupy, or use the USACE project, and the district engineer issues a written NWP verification.

32. Pre-Construction Notification.

(a) Timing. Where required by the terms of the NWP, the prospective permittee must notify the district engineer by submitting a pre-construction notification (PCN) as early as possible. The district engineer must determine if the PCN is complete within 30 calendar days of the date of receipt and, if the PCN is determined to be incomplete, notify the prospective permittee within that 30 day period to request the additional information necessary to make the PCN complete. The request must specify the information needed to make the PCN complete. As a general rule, district engineers will request additional information necessary to make the PCN complete only once. However, if the prospective permittee does not provide all of the requested information, then the district engineer will notify the prospective permittee that the PCN is still incomplete and the PCN review process will not commence until all of the requested information has been received by the district engineer. The prospective permittee shall not begin the activity until either:

(1) He or she is notified in writing by the district engineer that the activity may proceed under the NWP with any special conditions imposed by the district or division engineer; or

(2) 45 calendar days have passed from the district engineer's receipt of the complete PCN and the prospective permittee has not received written notice from the district or division engineer. However, if the permittee was required to notify the Corps pursuant to general condition 18 that listed species or critical habitat might be affected or are in the vicinity of the activity, or to notify the Corps pursuant to general condition 20 that the activity might have the potential to cause effects to historic properties, the permittee cannot begin the activity until receiving written notification from the Corps that there is "no effect" on listed species or "no potential to cause effects" on historic properties, or that any consultation required under Section 7 of the Endangered Species Act (see 33 CFR 330.4(f)) and/or section 106 of the National Historic Preservation Act (see 33 CFR 330.4(g)) has been completed. Also, work cannot begin under NWPs 21, 49, or 50 until the permittee has received written approval from the Corps. If the proposed activity requires a written waiver to exceed specified limits of an NWP, the permittee may not begin the activity until the district engineer issues the waiver. If the district or division engineer notifies the permittee in writing that an individual permit is required within 45 calendar days of receipt of a complete PCN, the permittee cannot begin the activity until an individual permit has been obtained. Subsequently, the permittee's right to proceed under the NWP may be modified, suspended, or revoked only in accordance with the procedure set forth in 33 CFR 330.5(d)(2).

(b) Contents of Pre-Construction Notification: The PCN must be in writing and include the following information:

(1) Name, address and telephone numbers of the prospective permittee;

(2) Location of the proposed activity;

(3) Identify the specific NWP or NWP(s) the prospective permittee wants to use to authorize the proposed activity;

(4) A description of the proposed activity; the activity's purpose; direct and indirect adverse environmental effects the activity would cause, including the anticipated amount of loss of wetlands, other special aquatic sites, and other waters expected to result from the NWP activity, in acres, linear feet, or other appropriate unit of measure; a description of any proposed mitigation measures intended to reduce the adverse environmental effects caused by the proposed activity; and any other NWP(s), regional general permit(s), or individual permit(s) used or intended to be used to authorize any part of the proposed project or any related activity, including other separate and distant crossings for linear projects that require Department of the Army authorization but do not require pre-construction notification. The description of the proposed activity and any proposed mitigation measures should be sufficiently detailed to allow the district engineer to determine that the adverse environmental effects of the activity will be no more than minimal and to determine the need for compensatory mitigation or other mitigation measures. For single and complete linear projects, the PCN must include the quantity of anticipated losses of wetlands, other special aquatic sites, and other waters for each single and complete crossing of those wetlands, other special aquatic sites, and other waters. Sketches should be provided when necessary to show that the activity complies with the terms of the NWP. (Sketches usually clarify the activity and when provided results in a quicker decision. Sketches should contain sufficient detail to provide an illustrative description of the proposed activity (e.g., a conceptual plan), but do not need to be detailed engineering plans);

(5) The PCN must include a delineation of wetlands, other special aquatic sites, and other waters, such as lakes and ponds, and perennial, intermittent, and ephemeral streams, on the project site. Wetland delineations must be prepared in accordance with the current method required by the Corps. The permittee may ask the Corps to delineate the special aquatic sites and other waters on the project site, but there may be a delay if the Corps does the delineation, especially if the project site is large or contains many wetlands, other special aquatic sites, and other waters. Furthermore, the 45 day period will not start until the delineation has been submitted to or completed by the Corps, as appropriate;

(6) If the proposed activity will result in the loss of greater than 1/10-acre of wetlands and a PCN is required, the prospective permittee must submit a statement describing how the mitigation requirement will be satisfied, or explaining why the adverse environmental effects are no more than minimal and why compensatory mitigation should not be required. As an alternative, the prospective permittee may submit a conceptual or detailed mitigation plan.

(7) For non-Federal permittees, if any listed species or designated critical habitat might be affected or is in the vicinity of the activity, or if the activity is located in designated critical habitat, the PCN must include the name(s) of those endangered or threatened species that might be affected by the proposed activity or utilize the designated critical habitat that might be affected by the proposed activity. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with the Endangered Species Act.

(8) For non-Federal permittees, if the NWP activity might have the potential to cause effects to a historic property listed on, determined to be eligible for listing on, or potentially eligible for listing on, the National Register of Historic Places, the PCN must state which historic property might have the potential to be affected by the proposed activity or include a vicinity map indicating the location of the historic property. For NWP activities that require pre-construction notification, Federal permittees must provide documentation demonstrating compliance with section 106 of the National Historic Preservation Act;

(9) For an activity that will occur in a component of the National Wild and Scenic River System, or in a river officially designated by Congress as a "study river" for possible inclusion in the system while the river is in an official study status, the PCN must identify the Wild and Scenic River or the "study river" (see general condition 16); and

(10) For an activity that requires permission from the Corps pursuant to 33 U.S.C. 408 because it will alter or temporarily or permanently occupy or use a U.S. Army Corps of Engineers federally authorized civil works project, the pre-construction notification must include a statement confirming that the project proponent has submitted a written request for section 408 permission from the Corps office having jurisdiction over that USACE project.

(c) Form of Pre-Construction Notification: The standard individual permit application form (Form ENG 4345) may be used, but the completed application form must clearly indicate that it is an NWP PCN and must include all of the applicable information required in paragraphs (b)(1) through (10) of this general condition. A letter containing the required information may also be used. Applicants may provide

electronic files of PCNs and supporting materials if the district engineer has established tools and procedures for electronic submittals.

(d) Agency Coordination:

(1) The district engineer will consider any comments from Federal and state agencies concerning the proposed activity's compliance with the terms and conditions of the NWP and the need for mitigation to reduce the activity's adverse environmental effects so that they are no more than minimal.

(2) Agency coordination is required for: (i) All NWP activities that require pre-construction notification and result in the loss of greater than 1/2-acre of waters of the United States; (ii) NWP 21, 29, 39, 40, 42, 43, 44, 50, 51, and 52 activities that require pre-construction notification and will result in the loss of greater than 300 linear feet of stream bed; (iii) NWP 13 activities in excess of 500 linear feet, fills greater than one cubic yard per running foot, or involve discharges of dredged or fill material into special aquatic sites; and (iv) NWP 54 activities in excess of 500 linear feet, or that extend into the waterbody more than 30 feet from the mean low water line in tidal waters or the ordinary high water mark in the Great Lakes.

(3) When agency coordination is required, the district engineer will immediately provide (e.g., via email, facsimile transmission, overnight mail, or other expeditious manner) a copy of the complete PCN to the appropriate Federal or state offices (FWS, state natural resource or water quality agency, EPA, and, if appropriate, the NMFS). With the exception of NWP 37, these agencies will have 10 calendar days from the date the material is transmitted to notify the district engineer via telephone, facsimile transmission, or email that they intend to provide substantive, site-specific comments. The comments must explain why the agency believes the adverse environmental effects will be more than minimal. If so contacted by an agency, the district engineer will wait an additional 15 calendar days before making a decision on the pre-construction notification. The district fully consider agency comments received within the specified time frame concerning the proposed activity's compliance with the terms and conditions of the NWPs, including the need for mitigation to ensure the net adverse environmental effects of the proposed activity are no more than minimal. The district engineer will provide no response to the resource agency, except as provided below. The district engineer will indicate in the administrative record associated with each pre-construction notification that the resource agencies' concerns were considered. For NWP 37, the emergency watershed protection and rehabilitation activity may proceed immediately in cases where there is an unacceptable hazard to life or a significant loss of property or economic hardship will occur. The district engineer will consider any comments received to decide whether the NWP 37 authorization should be modified, suspended, or revoked in accordance with the procedures at 33 CFR 330.5.

(4) In cases of where the prospective permittee is not a Federal agency, the district engineer will provide a response to NMFS within 30 calendar days of receipt of any Essential Fish Habitat conservation recommendations, as required by section 305(b)(4)(B) of the Magnuson-Stevens Fishery Conservation and Management Act.

5) Applicants are encouraged to provide the Corps with either electronic files or multiple copies of pre-construction notifications to expedite agency coordination.

Further Information

1. District Engineers have authority to determine if an activity complies with the terms and conditions of an NWP.
2. NWPs do not obviate the need to obtain other federal, state, or local permits, approvals, or authorizations required by law.
3. NWPs do not grant any property rights or exclusive privileges.
4. NWPs do not authorize any injury to the property or rights of others.
5. NWPs do not authorize interference with any existing or proposed Federal project (see general condition 31).

**2017 NATIONWIDE PERMITS
REGIONAL CONDITIONS
OMAHA DISTRICT
STATE OF MONTANA**

1. **PCN Requirement.** For all NWP's, permittees must notify the Corps in accordance with General Condition No. 32 (PCN) for regulated activities, located within or comprised of the following:

a. Wetlands Classified as Peatlands. Peatlands are seasonally waterlogged areas with a surface accumulation of peat (organic matter) 30 centimeters (12 inches) or more thick. Any peat-covered areas, including fens, bogs, and muskegs, are all peatlands.

i. PCN required for NWP 3, 5, 6, 20, 27, 32, and 38.

ii. All NWP's not listed above are revoked for use in peatlands.

b. Waters Adjacent to Natural Springs. Any projects located within 100 feet of the water source in natural spring areas. A spring is defined as any location where there is groundwater flow emanating from a distinct point. Springs do not include seeps or other groundwater discharge areas where there is no distinct point source.

c. Bank Stabilization Activities. Any project that involves bank stabilization greater than 300 linear feet or includes features that extend out from the existing bank line greater than 25% of the bankfull channel width.

d. Channel Straightening and Relocation Activities. Any project that involves straightening, relocating and/or shortening an existing perennial stream channel.

e. Tribal Reservations and Tribal Trust Lands. Any projects within the boundaries of any Tribal Reservation or Tribal trust lands.

f. Specific Waterways Requiring PCN. Any projects within the following waterways and their impoundments:

-Bitterroot River

-Clark Fork River (tributary to the
Columbia River)

-Flathead River

-Flathead Lake

-Milk River

-Missouri River

-Yellowstone River

2. **Bank and Shoreline Stabilization Activities.** The following additional requirements apply to all bank and shoreline stabilization:

a. The revetment must conform to the existing bankline; must not extend above the top of the bank (i.e. no new levees); and the slopes must be flatter than the angle of repose for the selected revetment material (i.e. rock riprap normally needs to be placed on a slope flatter than 1.5 Horizontal to 1 Vertical

(1.5H:1V).

- b. The revetment must not wholly or partially block flows from entering a side channel or an overflow channel.
3. **Counter-Sinking Riprap Associated with Culvert Installation.** When riprap inlet and outlet protection is used below the OHWM (OHWM), it must be placed to match the adjacent culvert bottom elevations. Where culvert bottom elevations are lower than the stream bed elevation, the riprap must match the culvert elevation.
4. **Placement and Removal of Temporary Fills.** Temporary fills in wetlands must be placed on a horizontal marker layer, such as fabric or certified weed-free straw, to delineate the pre-project ground elevation and facilitate complete fill removal and site restoration.
5. **Erosion and Sediment Control Blanket.** All erosion control blanket or fabric used in or adjacent to waters of the U.S. must be comprised of degradable material to ensure decomposition. Do not use material that includes stabilized netting or stabilized open mesh, as these products take a long time to degrade and they can trap small animals, birds, amphibians and fish. This prohibition also applies to mesh materials used for wattles, rolled materials, and bank wraps. Erosion control blanket or fabrics that break down within 24 months are acceptable. Non-degradable blankets or fabric may be allowed on a case-specific basis if it will be buried beneath riprap or structures and it is not likely to be exposed. Non-degradable blanket or fabric that becomes exposed within waters of the U.S. must be removed.
6. **Suitable Material.** NWP General Condition No. 6 prohibits the use of unsuitable material. Specific criteria can be found in the Omaha District's "Generic Prohibitions Regarding the Use of Certain Materials as Fill in Waters of the United States" and MT Department of Environmental Quality's (DEQ) "Specifications for use of Concrete Riprap for Streambank Stabilization," which apply to proposed work in jurisdictional waters.

REGIONAL CONDITIONS APPLICABLE TO SPECIFIC NATIONWIDE PERMITS

7. **NWP-3 – Maintenance and NWP-45 – Repair of Uplands Damaged by Discrete Events.** The definition of "discrete event," as used in these permits, includes, but is not limited to, unexpected natural and human-caused events such as fires, storms, landslides, avalanches, earthquakes, accidents, debris or ice jams, and floods. For the purpose of the NWPs, discrete event floods are stream flow events that overflow the OHWM.
8. **NWP-7 – Outfall Structures and Associated Intake Structures and NWP-12 – Utility Line Activities.** Inlet screens for intakes in the Yellowstone River or the Missouri River in Blaine, Chouteau, Custer, Dawson, Fergus, Garfield, McCone,

Petroleum, Phillips, Prairie, Richland, Roosevelt, Valley and Wibaux Counties must be installed on all pump intakes with a screen mesh opening size no larger than 0.25 inch. Water intake velocities must not exceed 0.5 foot per second through the mesh. Intakes must be located in the deepest water available and be elevated off the bottom of the river bed.

REGIONAL CONDITIONS APPLICABLE ONLY TO THE SPECIAL RIVER MANAGEMENT ZONE OF THE UPPER YELLOWSTONE RIVER

Special River Management Zone (SRMZ) of the Upper Yellowstone River is defined within the Special Area Management Plan (SAMP) as the 48-mile reach of the upper Yellowstone River (River Miles 531.8 to 483.6) from upstream of Emigrant River downstream to a few miles below the Shields River and Mission Creek confluences (0.7 miles downstream from the bridge at the community of Springdale). It includes secondary channels, side channels, and the main (primary) channels, and adjacent wetlands within the channel migration zone (CMZ) or, in absence of a CMZ, within areas flooded by the 100-year discharge. The SRMZ is located entirely within Park County.

In addition to Regional Conditions 1 through 8, the following Regional Conditions 9 through 24 apply within the SRMZ described above:

9. **SRMZ – Notification – All NWP's.** Permittees must notify the Corps in accordance with General Condition No. 32 (PCN) for any regulated activity in waters of the U.S. within the SRMZ. This includes all activities within the Yellowstone River, the portions of tributaries within the SRMZ, and wetlands within the SRMZ.
10. **SRMZ – Emergency Work.** Activities requiring a Department of the Army (DA) Permit that is necessary to prevent imminent loss of life or property is allowed within the SRMZ. Contact the Corps as soon as reasonably possible by telephone at 406-441-1375 and/or by Fax at 406-441-1380. Contact may also be made in person or by sending an e-mail to: CENWO.ODRMT@usace.army.mil. All such work will be fully reviewed under the SAMP provisions.
11. **SRMZ - NWP's Revoked for Use.** The following NWP's have been revoked for all waters and activities within the 48-mile SRMZ:
 - NWP 17 - Hydropower Projects**
 - NWP 21 - Surface Coal Mining Activities**
 - NWP 29 - Residential Developments**
 - NWP 39 - Commercial and Institutional Developments**
 - NWP 42 - Recreational Facilities**
 - NWP 43 - Stormwater Management Facilities**
 - NWP 44 - Mining Activities**
 - NWP 45 - Repair of Uplands Damaged by Discrete Events**
 - NWP 49 - Coal Remining Activities**

NWP 50 - Underground Coal Mining Activities

12. **SRMZ – Activities Requiring Individual Permit Review.** The following project activities are not authorized under a NWP in the SRMZ. These projects typically have more than minimal adverse impacts and must be reviewed under standard (individual) permit procedures.

- a. New dams, new diversions, and/or new impoundments for any purpose;
- b. Construction of ponds and new artificial stream channels, unless they are necessary and appropriate elements of a stream or wetland restoration project;
- c. Hydraulic dredging and mining and mechanical excavation to obtain aggregate, fill material, or minerals, including gold. Processing of material for the purpose of obtaining select minerals or a specific gradation of material, where only a portion of the sediment or alluvium is removed and the remainder returned to the SRMZ, is not allowed under a NWP in the SRMZ.

13. **SRMZ - Bank Stabilization Activities - All NWPs.** For bank stabilization activities associated with any NWP, including maintenance of bank stabilization, the following Regional Conditions apply:

For bank revetments such as riprap, root wads, bioengineered revetments, or combination revetments, a. through e. apply:

- a. Revetments must conform to the existing eroded or eroding bankline, unless such work is determined by the Corps to be biologically or geomorphically beneficial for the upper Yellowstone River.
- b. Revetment slopes must be flatter than the angle of repose for the selected revetment material. For example, rock riprap normally needs to be placed on a slope flatter than 1.5H:1V.
- c. Revetments are only permissible under NWPs if they are parallel to and near the lateral boundaries of the SRMZ.
- d. Revetments must not extend above the elevation of the adjacent natural bank height (i.e., no new levees).
- e. Revetments must not wholly or partially block flows from entering a side channel, secondary channel, or an overflow channel, unless such work is determined by the Corps to be necessary for maintaining or restoring the geomorphic integrity of the upper Yellowstone River.

For bank stabilization structures that project into the stream, such as weirs, barbs, vanes, or hard points, f. through k. apply:

- f. Bank stabilization structures must not wholly or partially block flows from entering a side channel, secondary channel, or an overflow channel, unless such work is determined by the Corps to be necessary for maintaining or restoring the geomorphic integrity of the upper Yellowstone River.

- g. Bank stabilization structures are only permissible under NWP's if they result in an effective bankline that is approximately parallel to and near the lateral boundaries of the CMZ.
 - h. Bank stabilization structures must be keyed into the bank far enough to prevent flanking.
 - i. Bank stabilization structures cannot occupy more than 10% of the bankfull channel area. Bankfull channel area pertains to the specific primary or secondary channel in question, and is not the aggregate channel area of all primary and secondary channels in multi-channel reaches.
 - j. Bank stabilization structures must not present hazardous obstructions to boating, floating, or other river uses.
 - k. Bank stabilization structures that are low in elevation, project only a short distance out from the bank, and angle upstream are more likely to qualify for NWP's because they typically result in less adverse impact on aquatic resources than structures that are tall, long, and point downstream.
14. **SRMZ – Temporary Bank Stabilization – All NWP's.** Temporary bank stabilization is prohibited during seasonal high flows.
15. **SRMZ – Sediment Management – All NWP's.** Sediment removal is allowable only to maintain function of existing facilities and structures, or as necessary to maintain or restore the geomorphic integrity of the upper Yellowstone River. Diversion or removal of sediment or alluvium from the river channel and adjacent wetlands for other purposes is not allowed in the SRMZ under any NWP.
16. **SRMZ – Temporary Vegetation Impacts – All NWP's.** Limit clearing of riparian or wetland vegetation to the absolute minimum necessary. Where temporary riparian or wetland vegetation impacts are unavoidable, mow or cut off the vegetation above the ground, leaving the topsoil and root mass intact. Restore temporarily disturbed areas to original contours and use seeding and planting as necessary to re-establish desirable vegetative cover, utilizing native species in areas where native species were impacted.
17. **SRMZ – NWP-11 – Temporary Recreational Structures.** Temporary recreational structures can be installed no earlier than seven (7) calendar days in advance of an event and must be removed no later than seven (7) calendar days after the event concludes.
18. **SRMZ – NWP-12 – Utility Line Activities.** Trench excavation and backfill for utility lines is prohibited within the OHWM of main and secondary flow channels and in adjacent wetlands.
19. **SRMZ – NWP-13 – Bank Stabilization.** Construction of temporary or permanent levees is prohibited. Only bank stabilization that is parallel to and adjacent to the valley wall and/or SRMZ boundary is allowed. All other bank stabilization must be reviewed under standard (individual) permit procedures. Bank stabilization along

existing roads, ditches, fills, and structures already located along the valley wall is allowed under this Permit.

20. **SRMZ – NWP-14 – Linear Transportation Projects.** The construction of new transportation facilities in waters of the U.S. is prohibited under this NWP and must be reviewed under standard (individual) permit procedures. The expansion, modification, improvement, replacement, reconstruction, and upgrading of existing transportation facilities are allowed under this NWP within the SRMZ.
21. **SRMZ – NWP- 27 – Aquatic Habitat Restoration, Establishment, and Enhancement Activities.** The construction of water control structures, dikes, berms, current deflectors, bank stabilization, and ponds is prohibited within the CMZ of the upper Yellowstone River unless it is demonstrated the proposed features contribute to the restoration or rehabilitation of previously lost or impaired functions of the upper Yellowstone River and adjacent aquatic areas.
22. **SRMZ – NWP-30 – Moist Soil Management for Wildlife.** Fire breaks within the CMZ of the upper Yellowstone River must be reclaimed and restored within six (6) months after the fire event ends.
23. **SRMZ – NWP-33 – Temporary Construction, Access, and Dewatering.** Construction of temporary levees and other structures or fills in waters of the U.S. that prevent or reduce overbank flow is prohibited.
24. **SRMZ – NWP 40 – Agricultural Activities.** Only those activities associated with the reduction of existing adverse impacts on the upper Yellowstone River may be authorized by this NWP. Examples of potentially allowable projects include work associated with livestock management; moving livestock watering areas off the river or out of the CMZ; removal of irrigation systems from the CMZ; and the removal or conversion of irrigation systems from flood irrigation to sprinkler irrigation.